| Laboratory | Bhargava Building Atelier (P) Ltd., Argade ki Gali, Dal Bazar Tiraha, Gwalior, Madhya Pradesh | | |
|------------------------|--|----------------------------|--|
| Accreditation Standard | ISO/IEC 17025: 2005 | | |
| Certificate Number | TC-6706 (in lieu of T-2707) | Page 1 of 3 | |
| Validity | 24.11.2017 to 23.11.2019 | Last Amended on 03.01.2018 | |

| SI. | Product / Material of Test | Specific Test Performed | Test Method Specification against which tests are | Range of Testing / Limits of Detection |
|-----|-------------------------------|----------------------------|--|---|
| | | | performed | |

MECHANICAL TESTING

| I. | BUILDING MATERI | ALS | | |
|-----|------------------------------------|--------------------------------------|------------------------|--|
| 1. | Cement | Standard Consistency | IS 4031 : Part-4 | 23% to 35% |
| | (OPC 53 Grade / 43 Grade & PPC) | Initial Setting Time | IS 4031 : Part-5 | 30 minutes to 300 minutes |
| | | Final Setting Time | IS 4031 : Part-5 | 30 minutes to 600 minutes |
| | | Compressive Strength | IS 4031 : Part-6 | 10 N/mm ² to 80 N/mm ² |
| | | Soundness a)Le-chatelier's Method | IS 4031 : Part-3 | 0.10 mm to 10 mm |
| 2. | Concrete | Compressive Strength | IS 516 | 1 Mpa to 75 Mpa |
| 3. | Fine Aggregates | Sieve Analysis | IS 2386 Part 1 | 0.150 mm to 4.75 mm |
| | | Water Absorption | IS 2386 : Part 3 | 0.1 % to 3 % |
| | | Specific Gravity | IS 2386 : Part 3 | 1.0 g/cc to 3.0 g/cc |
| | | Bulk Density | IS 2386 : Part 3 | 1.0 g/cc to 2.0 g/cc |
| 4. | Coarse | Sieve Analysis | IS 2386 Part 1 | 4.75 mm to 125 mm |
| | Aggregates | Water Absorption | IS 2386 : Part 3 | 0.1 % to 10 % |
| | | Flakiness Index | IS 2386 Part 1 | 1 % to 100 % |
| | | Elongation Index | IS 2386 Part 1 | 1 % to 100 % |
| | | Crushing Value | IS 2386 Part 4 | 1 % to 50 % |
| | | Impact Value | IS 2386 Part 4 | 1 % to 50 % |
| | | Specific Gravity | IS 2386 : Part 3 | 1.0 to 4.0 |
| | | Bulk Density | IS 2386 : Part 3 | 2 g/cc to 4 g/cc |
| 5. | Bitumen | Bitumen Content % | ASTM D 2172 | 1% to 10 % |
| II. | SOIL AND ROCK | | | |
| 1. | Soil | Moisture Analysis | IS 2720 Part 2 | 1 % to 30 % |
| | | Liquid Limit | IS 2720 : Part 5 | 20 % to 80 % |
| | | Plastic Limit | IS 2720 : Part 5 | 15 % to 60 % |
| | | Specific Gravity | IS 2720 : Part 3/Sec 2 | 1.5 g/cc to 3 g/cc |

| Laboratory | Bhargava Building Atelier (P) Ltd., Argade ki Gali, Dal Bazar Tiraha, Gwalior, Madhya Pradesh | | |
|------------------------|--|----------------------------|--|
| Accreditation Standard | ISO/IEC 17025: 2005 | | |
| Certificate Number | TC-6706 (in lieu of T-2707) | Page 2 of 3 | |
| Validity | 24.11.2017 to 23.11.2019 | Last Amended on 03.01.2018 | |

| SI. | Product / Material of Test | Specific Test Performed | Test Method Specification against which tests are performed | Range of Testing / Limits of Detection |
|------|-------------------------------|---|---|--|
| | | Grain Size Analysis | IS 2720 : Part 4 | 4.75 mm to 75 micron |
| | | Free Swell Index | IS 2720 : Part 40 | 1% to 100% |
| | | Swelling Pressure | IS 2720 : Part 41 | 0.1 kg/Sq.cm to 2.0 kg/Sq.cm |
| | | Consolidation Test | IS 2720 : Part 15 | 0.1 kg/Sq.cm to 38 kg/Sq.cm |
| | | Direct Shear Test | IS 2720 : Part 13 | C : Up to 1.0 kg/Sq.cm _{\varphi} : 5° to 45° |
| | | Triaxial Test with Pore Pressure measurement | IS 2720: Part 12 | C : Up to 2.0 kg/Sq.cm $_{\phi}$: 5° to 40° |
| | | Light Compaction | IS 2720 : Part 7 | MDD: 1.40 g/cc to 2.0 g/cc OMC: 10 % to 30 % |
| | | Heavy Compaction | IS 2720 : Part 8 | MDD: 1.40 g/cc to 2.5 g/cc OMC: 10 % to 30 % |
| | | CBR | IS 2720 : Part 16 | 0.5 % to 35 % |
| III. | MECHANICAL PRO | PERTIES OF METALS | 1 | |
| 1. | Reinforcement Steel | Ultimate Tensile Strength | IS 1608 | 10 to 40 kN/0.10 kN 20 to 100 kN/0.25 kN 20 to 200kN/0.50 kN 20 to 400kN/1.0 kN @ 100 to 700 N/mm ² |
| | | Yield Stress | IS 1608 | 10 to 40 kN/0.10 kN 20 to 100 kN/0.25 kN 20 to 200 kN/0.50 kN 20 to 400 kN/1.0 kN @ 100 to 700 N/mm ² |
| | | % Elongation | IS 1786 | 10 to 40 kN/0.10 kN 20 to 100 kN/0.25 kN 20 to 200 kN/0.50 kN 20 to 400 kN/1.0 kN @ 12 % to 30 % |

| Lal | boratory | Bhargava Building Atelier (P) Ltd., Argade ki Gali, Dal Bazar Tiraha, Gwalior, Madhya Pradesh | | | |
|--------------------|-------------------------------|--|---|----------------------------|---|
| Ac | creditation Standard | ISO/IEC 17025: 2 | 2005 | | |
| Certificate Number | | TC-6706 (in lieu of T-2707) | | Page 3 of 3 | |
| Validity | | 24.11.2017 to 23.11.2019 | | Last Amended on 03.01.2018 | |
| SI. | Product / Material of Test | Specific Test Performed | Test Method S against which performed | | Range of Testing / Limits of Detection |

| | | performed | |
|--|----------------|-----------|-------------------------|
| | Mass Per Meter | IS 1786 | 50 g to 30 kg/m / 0.5 g |
| | Bend Test | IS 1599 | 22.5 mm, 30 mm & |
| | De Der d Teet | 10.4700 | 50 mm mandrel size |
| | Re-Bend Test | IS 1786 | 22.5 mm, 30 mm & |
| | | | 50 mm mandrel size |