



(A Constituent Board of Quality Council of India)



SCOPE OF ACCREDITATION

Laboratory Name QUALITY CONTROL LABORATORIES, CHANDERIA CEMENT WORKS, P.O.

CEMENT FACTORY, MADHAV NAGAR, SECTOR- I, CHITTORGARH, RAJASTHAN,

INDIA

Accreditation Standard ISO/IEC 17025:2017

Certificate Number TC-5470 Page No.: 1 / 4

S.No	Discipline / Group	Product / Material of Test	Specific Test Performed	Test Method Specification against which tests are performed	Range of Testing/ Limits of Detection		
	Permanent Facility						
1	CHEMICAL- BUILDING MATERIAL	OPC 53	Al2O3	IS 4032: 2014	0.2 % to 10.0 %		
2	CHEMICAL- BUILDING MATERIAL	OPC 53	CaO	IS 4032: 2014	55.0 % to 68.0 %		
3	CHEMICAL- BUILDING MATERIAL	OPC 53	CI	IS 4032: 2014	0.005 % to 1.000 %		
4	CHEMICAL- BUILDING MATERIAL	OPC 53	Fe2O3	IS 4032: 2014	0.1 % to 6.0 %		
5	CHEMICAL- BUILDING MATERIAL	OPC 53	IR	IS 4032: 2014	0.1 % to 8.0 %		
6	CHEMICAL- BUILDING MATERIAL	OPC 53	LOI	IS 4032: 2014	0.1 % to 0.8 %		
7	CHEMICAL- BUILDING MATERIAL	OPC 53	MgO	IS 4032: 2014	0.1 % to 10.0 %		
8	CHEMICAL- BUILDING MATERIAL	OPC 53	SiO2	IS 4032: 2014	15.0 % to 28.0 %		
9	CHEMICAL- BUILDING MATERIAL	OPC 53	SO3	IS 4032: 2014	0.1 % to 6.0 %		
10	CHEMICAL- BUILDING MATERIAL	OPC-43	Al2O3	IS 4032: 2014	0.2 % to 10.0 %		
11	CHEMICAL- BUILDING MATERIAL	OPC-43	CaO	IS 4032: 2014	55.0 % to 68.0 %		
12	CHEMICAL- BUILDING MATERIAL	OPC-43	CI	IS 4032: 2014	0.005 % to 1.0 %		
13	CHEMICAL- BUILDING MATERIAL	OPC-43	Fe2O3	IS 4032: 2014	0.1 % to 6.0 %		





(A Constituent Board of Quality Council of India)



SCOPE OF ACCREDITATION

Laboratory Name QUALITY CONTROL LABORATORIES, CHANDERIA CEMENT WORKS, P.O.

CEMENT FACTORY, MADHAV NAGAR, SECTOR-I, CHITTORGARH, RAJASTHAN,

INDIA

Accreditation Standard ISO/IEC 17025:2017

Certificate Number TC-5470 Page No.: 2 / 4

S.No	Discipline / Group	Product / Material of Test	Specific Test Performed	Test Method Specification against which tests are performed	Range of Testing/ Limits of Detection
14	CHEMICAL- BUILDING MATERIAL	OPC-43	IR	IS 4032: 2014	0.1 % to 8.0 %
15	CHEMICAL- BUILDING MATERIAL	OPC-43	LOI	IS 4032: 2014	0.1 % to 8.0 %
16	CHEMICAL- BUILDING MATERIAL	OPC-43	MgO	IS 4032: 2014	0.1 % to 10.0 %
17	CHEMICAL- BUILDING MATERIAL	OPC-43	SiO2	IS 4032: 2014	15.0 % to 28.0 %
18	CHEMICAL- BUILDING MATERIAL	OPC-43	SO3	IS 4032: 2014	0.1 % to 6.0 %
19	CHEMICAL- BUILDING MATERIAL	PPC Pt-1	CI	IS 4032: 2014	0.005 % to 1.0 %
20	CHEMICAL- BUILDING MATERIAL	PPC Pt-1	IR	IS 4032: 2014	15.0 % to 40.0 %
21	CHEMICAL- BUILDING MATERIAL	PPC Pt-1	LOI	IS 4032: 2014	0.10 % to 10.0 %
22	CHEMICAL- BUILDING MATERIAL	PPC Pt-1	MgO	IS 4032: 2014	0.1 % to 10.0 %
23	CHEMICAL- BUILDING MATERIAL	PPC Pt-1	SO3	IS 4032: 2014	0.1 % to 6.0 %
24	MECHANICAL- BUILDINGS MATERIALS	OPC 43	Autoclave expansion	IS 4031: 2014	0.001 % to 2.0 %
25	MECHANICAL- BUILDINGS MATERIALS	OPC 43	Fineness	IS 4031: 2013	100 m²/kg to 800 m²/kg
26	MECHANICAL- BUILDINGS MATERIALS	OPC 43	Initial Setting Time (Minutes)	IS 4031: 2014	15 minutes to 250 minutes





(A Constituent Board of Quality Council of India)



SCOPE OF ACCREDITATION

Laboratory Name QUALITY CONTROL LABORATORIES, CHANDERIA CEMENT WORKS, P.O.

CEMENT FACTORY, MADHAV NAGAR, SECTOR-I, CHITTORGARH, RAJASTHAN,

INDIA

Accreditation Standard ISO/IEC 17025:2017

Certificate Number TC-5470 Page No.: 3 / 4

S.No	Discipline / Group	Product / Material of Test	Specific Test Performed	Test Method Specification against which tests are performed	Range of Testing/ Limits of Detection
27	MECHANICAL- BUILDINGS MATERIALS	OPC 43	Soundness by Le- chatelier expansion (mm)	IS 4031: 2014	0.5 mm to 30.0 mm
28	MECHANICAL- BUILDINGS MATERIALS	OPC 43	Standard Consistency	IS 4031: 2014	10 % to 35 %
29	MECHANICAL- BUILDINGS MATERIALS	OPC 53	Autoclave expansion	IS 4031: 2014	0.001 % to 2.000 %
30	MECHANICAL- BUILDINGS MATERIALS	OPC 53	Compressive Strength	IS 4031: 2014	14 MPa to 80 MPa
31	MECHANICAL- BUILDINGS MATERIALS	OPC 53	Final Setting Time	IS 4031: 2014	30 minutes to 600 minutes
32	MECHANICAL- BUILDINGS MATERIALS	OPC 53	Fineness	IS 4031: 2013	100 m²/kg to 800 m²/kg
33	MECHANICAL- BUILDINGS MATERIALS	OPC 53	Initial Setting Time	IS 4031: 2014	15 minutes to 250 minutes
34	MECHANICAL- BUILDINGS MATERIALS	OPC 53	Soundness by Lechatelier expansion	IS 4031: 2014	0.5 % to 30.0 %
35	MECHANICAL- BUILDINGS MATERIALS	OPC 53	Standard Consistency	IS 4031: 2014	10 % to 35 %
36	MECHANICAL- BUILDINGS MATERIALS	OPC43	Compressive Strength	IS 4031: 2014	14 Mpa to 80 Mpa





(A Constituent Board of Quality Council of India)



SCOPE OF ACCREDITATION

Laboratory Name QUALITY CONTROL LABORATORIES, CHANDERIA CEMENT WORKS, P.O.

CEMENT FACTORY, MADHAV NAGAR, SECTOR-I, CHITTORGARH, RAJASTHAN,

INDIA

Accreditation Standard ISO/IEC 17025:2017

Certificate Number TC-5470 Page No.: 4 / 4

S.No	Discipline / Group	Product / Material of Test	Specific Test Performed	Test Method Specification against which tests are performed	Range of Testing/ Limits of Detection
37	MECHANICAL- BUILDINGS MATERIALS	OPC43	Final Setting Time	IS 4031: 2014	30 minutes to 600 minutes
38	MECHANICAL- BUILDINGS MATERIALS	PPC Pt-1	Autoclave expansion	IS 4031: 2014	0.001 % to 2.000 %
39	MECHANICAL- BUILDINGS MATERIALS	PPC Pt-1	Compressive Strength	IS 4031: 2014	14 MPa to 80 MPa
40	MECHANICAL- BUILDINGS MATERIALS	PPC Pt-1	Final Setting Time	IS 4031: 2014	30 minutes to 600 minutes
41	MECHANICAL- BUILDINGS MATERIALS	PPC Pt-1	Fineness	IS 4031: 2013	100 m²/kg to 800 m²/kg
42	MECHANICAL- BUILDINGS MATERIALS	PPC Pt-1	Initial Setting Time	IS 4031: 2014	15 minutes to 250 minutes
43	MECHANICAL- BUILDINGS MATERIALS	PPC Pt-1	Soundness by Lechatelier expansion	IS 4031: 2014	0.5 mm to 30.0 mm
44	MECHANICAL- BUILDINGS MATERIALS	PPC Pt-1	Standard Consistency	IS 4031: 2014	10 % to 35 %