Laboratory			JK Lakshmi Cement Limited, Physical Laboratory, P.O. Jaykaypuram, Dist. Sirohi, Rajasthan			
Accreditation Standard		ard ISO/IEC 17025: 2005	ISO/IEC 17025: 2005			
Discipline		Mechanical Testing	Iss	sue Date	26.08.2015	
Certificate Number		T-0720	Va	lid Until	25.08.2017	
Last	Amended on	11.09.2015	Ра	ge	1 of 1	
S.No.	Product / Material of Test	Specific Test Performed	Test Method Specification against which tests are performed		of Testing / of Detection	
I.	BUILDING MATERIALS					
1.	Cement (OPC, PPC)	Determination of fineness by Blaine Air Permeability Method	IS 4031 (Part 2): 1999 (RA 2013	$3) 200 \text{ m}^2$	$200\ m^2/kg$ to $400\ m^2/kg$	
		Determination of Consistency of Standard Cement Paste	IS 4031 (Part 4): 1988 (RA 2014	4) 20 % to	20 % to 40 %	
		Setting Time Initial Final	IS 4031 (Part 5): 1988 (RA 2014	4) 30 min	to 720 min	
		Soundness by Lechatlier and	IS 4031 (Part 3): 1988 (RA 2014	4) 0 to 20	mm	
		By Autoclave	IS 4031 (Part 3): 1988 (RA 2014	4) 0 to 4.0	%	
		Compressive Strength	IS 4031 (Part 6): 1988 (RA 2014) 2 MPa	to 65 MPa	
2.	Cement (PPC)	Drying Shrinkage	IS 4031 (Part 10): 1988 (RA 2014)	0 to 0.2	0 to 0.20 %	
3.	Pozzolana Material	Lime Reactivity Test	IS 1727: 1967 (RA 2013)	4.5 MP	4.5 MPa to 15 MPa	

##