Laboratory	DTPS Coal Testing Laboratory, 4th Floor, Service Building, Dahanu Thermal Power Station (DTPS), Reliance Infrastructure Ltd., Dahanu Road, Distt. Palghar, Maharashtra		
Accreditation Standard	ISO/IEC 17025: 2005		
Certificate Number	TC-6307 (in lieu of T-2694)	Page 1 of 1	
Validity	14.10.2017 to 13.10.2019	Last Amended on	

ſ	SI.	Product / Material	Specific Test Performed	Test Method Specification	Range of Testing /
		of Test	-	against which tests are	Limits of Detection
				performed	

CHEMICAL TESTING

1.	Coal	Total Moisture	IS: 1350 (Part 1) – 1984. (Reaffirmed 2013)	5% to 50 %
		Moisture in Analysis Sample	IS: 1350 (Part 1) – 1984. (Reaffirmed 2013)	1% to 30 %
		Ash	IS: 1350 (Part 1) – 1984. (Reaffirmed 2013)	1% to 50 %
		Volatile Matter	IS: 1350 (Part 1) – 1984. (Reaffirmed 2013)	15% to 45 %
		Fixed Carbon	IS: 1350 (Part 1) – 1984. (Reaffirmed 2013)	20% to 60 %
		Gross Calorific Value.	IS: 1350 (Part II) – 1970. (Reaffirmed 2015)	2500 Kcal/Kg to 8000 Kcal/Kg
		Sulphur	IS: 1350(Part III) – 1969. (Reaffirmed 2015)	0.05% to 1.5 %