| Laboratory | Stedrant Technoclinic Pvt. Ltd, Shed No. F-3/A, IDA Nacharam, Street No.10, Hyderabad, Telangana | | |
|------------------------|---|----------------------------------|--|
| Accreditation Standard | ISO/IEC 17025: 2005 | | |
| Certificate Number | TC-7523 | Page 1 of 6 | |
| Validity | 04.07.2018 to 03.07.2020 | Last Amended on | |
| SL Product / Material | Specific Test Method | Specification Range of Testing / | |

| S | i. | Product / Material | Specific Test | Test Method Specification | Range of Testing / |
|---|----|--------------------|---------------|---------------------------|---------------------|
| | | of Test | Performed | against which tests are | Limits of Detection |
| | | | | performed | |

MECHANICAL TESTING

| I. | BUILDING MATERIA | ALS | | |
|----|------------------|------------------------------------|------------------|---|
| 1. | Aggregate Coarse | Sieve Analysis | IS 2386 (Part 1) | Upto 100 % (2.36 mm to 125 mm) |
| | | Specific gravity | IS 2386 (Part 3) | 2.0 to 4.0 |
| | | Bulk Density (Loose &Rodded) | IS 2386 (Part 3) | 1.0 kg/L to 4.0 kg/L |
| | | Flakiness Index | IS 2386 (Part 1) | Upto 50 % |
| | - | Elongation Index | IS 2386 (Part 1) | Upto 50 % |
| | - | Water Absorption | IS 2386 (Part 3) | 0.1 % to 5 % |
| | - | Impact value | IS 2386 (Part 4) | 1 % to 60 % |
| | - | Los Angeles Abrasion | IS 2386 (Part 4) | 1 % to 60 % |
| | - | Crushing Value | IS 2386 (Part 4) | 1 % to 60 % |
| | - | 10 % Fines Value | IS 2386 (Part 4) | 50 kN to 700 kN |
| | | Material finer than 75 | IS 2386 (Part 1) | Upto 10 % |
| 2. | Aggregate Fine | Sieve analysis | IS 2386 (Part 1) | Upto 100 % (75 µm to 6.3 mm) |
| | | Specific gravity | IS 2386 (Part 3) | 2.0 to 4.0 |
| | | Bulk density (Loose and Rodded) | IS 2386 (Part 3) | 1.0 kg/L to 4.0 kg/L |
| | | Bulking | IS 2386 (Part 3) | 1 % to 50 % |
| | | Water absorption | IS 2386 (Part 3) | 0.1 % to 10 % |
| | | Material finer than 75 µm | IS 2386 (Part 1) | Upto 30 % |
| 3. | Bricks | Water absorption | IS 3495 (Part 2) | 1 % to 40 % |
| | | Compressive strength | IS 3495 (Part 1) | 1 N/mm ² to 35N/mm ² |
| | | Efflorescence | IS 3495 (Part 3) | Qualitative |
| 4. | Hardened | Compressive strength | IS 516 | 5 N/mm ² to100 N/mm ² |
| | Concrete | Flexural strength | IS 516 | 1 N/mm ² to 15 N/mm ² |

| Laboratory | Stedrant Technoclinic Pvt. Ltd, Shed No. F-3/A, IDA Nacharam, Street No.10, Hyderabad, Telangana |
|------------------------|---|
| Accessitation Standard | |

| Accreditation Standard | ISO/IEC 17025: 2005 |
|------------------------|--------------------------|
| Certificate Number | TC-7523 |
| Validity | 04.07.2018 to 03.07.2020 |

Page 2 of 6

Last Amended on --

| l. | Product / Material of Test | Specific Test Performed | Test Method Specification against which tests are performed | Range of Testing / Limits of Detection |
|----|-------------------------------------|--|---|---|
| | (Concrete Cubes and Cores) | Splitting Tensile Strength | IS 5816 | 0.5 N/mm ² to 12 N/mm ² |
| | | Modulus of Elasticity | IS 516 | 20000 N/mm ² to 70000 N/mm ² |
| 5. | Burnt Clay Hollow | Compressive Strength | IS 3952 (Annexure A) | 1 N/mm ² to 35 N/mm ² |
| | Bricks and Blocks | Water Absorption | IS 3952 (Annexure B) | 2 % to 30 % |
| 6. | Hydraulic Cement | Consistency | IS 4031(Part 4) | 10 % to 40 % |
| | | Initial setting time | IS 4031 (Part 5) | 5 minute to 400 minute |
| | | Final setting time | IS 4031 (Part 5) | 35 minute to 800 minute |
| | | Fineness (by Blaine's method) | IS 4031 (Part 2) | 100 m ² /kg to 600 m ² /kg |
| | • | Compressive strength | IS 4031(Part 6) | 1 N/mm ² to 80 N/mm ² |
| | | Soundness by Le– Chatelier's method | IS 4031 (Part 3) | 0.5 mm to 10 mm |
| | - | Soundness by Autoclave method | IS 4031 (Part 3) | 0.01 % to 2 % |
| | | Density | IS 4031 (Part 11) | 2.0 g/cc to 4.0 g/cc |
| 7. | Bituminous Mix | Binder Content | ASTM D 2172 IRC SP112 | 1 % to 8 % |
| | | Density | ASTM D2726-17 | 1.8 g/cc to 3.0 g/cc |
| 8. | Pozzolana–Flyash, Silica Fume | Fineness (by Blaine's Method) | IS 1727 | 100 m ² /kg to 700 m ² /kg |
| | | Specific gravity | IS 1727 | 1 to 3 |
| | - | Residue on 45 µm sieve (Wet) | IS 1727 | 0.1 % to 50 % |
| 9. | Hollow and Solid Concrete Blocks | Water absorption | IS 2185 (Part 1) Annexure–E | 1 % to 20 % |
| | - | Dimensional Analysis | IS 2185 (Part 1) Annexure –B | 50 mm to 450 mm |
| | | Compressive Strength | IS 2185 (Part 1) Annexure –D | 1.0 N/mm ² to 20 N/mm ² |
| | | Block Density | IS 2185 (Part 1) Annexure –E | 1000 kg/m ³ to 2800 kg/m ³ |

| Laboratory | Stedrant Technoclinic Pvt. Ltd, Shed No. F-3/A, IDA Nacharam, Street No.10, Hyderabad, Telangana |
|------------------------|---|
| Accreditation Standard | ISO/IEC 17025: 2005 |

Certificate Number TC-7523

Validity

04.07.2018 to 03.07.2020

Page 3 of 6

Last Amended on --

| SI. | Product / Material of Test | Specific Test Performed | Test Method Specification against which tests are performed | Range of Testing / Limits of Detection |
|-----|-------------------------------------|---|---|---|
| 10. | Pavers Block | Water Absorption | IS 15658 | 0.1 % to 20 % |
| | | Compressive Strength | IS 15658 | 1 N/mm ² to 75 N/mm ² |
| 11. | Autoclaved | Block Density | IS 6441 (Part 1) | 450kg/m ³ to 1000 kg/m ³ |
| | Aerated Concrete Blocks | Compressive Strength | IS 6441 (Part 5) | 0.5 N/mm ² to12 N/mm ² |
| II. | SOIL & ROCK | | | |
| 1. | Soil, Granular Sub | Liquid Limit | IS 2720 (Part 5) | 20 % to 100 % |
| | Base, Wet Mix | Plastic Limit | IS 2720 (Part 5) | 10 % to 70 % |
| | Macadam | Moisture content | IS 2720 (Part 2) | 1 % to 40 % |
| | | Grain size analysis | IS 2720 (Part 4) | 0.1 % to 100 % (0.075 mm to 63 mm) |
| | | Particle Size Analysis by Hydrometer method | IS 2720 (Part 4) | 0.1% to 100 % (0.002 mm to 0.075 mm) |
| | | Specific gravity | IS 2720 (Part 3 / Section 1) | 2.0 to 3.0 |
| | | Proctor Density (Light Compaction) | IS 2720 (Part 7) | OMC= 4 % to 30 % MDD= 1.2 g/cc to 2.5 g/cc |
| | | Proctor Density (Heavy Compaction) | IS 2720 (Part 8) | OMC= 4 % to 25 % MDD= 1.3 g/cc to 2.6 g/cc |
| | | CBR | IS 2720 (Part 16) | 1 % to 100 % |
| | | Free swell index | IS 2720 (Part 40) | 0.5 % to 200 % |
| 2. | Soil, Granular Sub Base, Wet Mix | Field Density (by core cutter method) | IS 2720 (Part 29) | 1.3 g/cc to 2.4 g/cc |
| | Macadam (at site) | Field density (by sand replacement method) | IS 2720 (Part 28) | 1.3 g/cc to 2.8 g/cc |
| 3. | Natural Building stone | Compressive strength | IS 1121 (Part 1) | 100 kg/cm ² to 1200 kg/cm ² |
| | | Water absorption | IS 1124 | 1 % to 10 % |
| | | True specific gravity | IS 1122 | 1 to 4 |
| 4. | Rock | Unconfined Compressive Strength | IS 9143 | 1 N/mm ² to 250N/mm ² |
| | | Water Content | IS 13030 | 0.1 % to 50 % |
| | | Density | IS 13030 | 1000 kg/m ³ to 5000kg/m ³ |

| Laboratory | Stedrant Technoclinic Pvt. Ltd, Shed No. F-3/A, IDA Nacharam, Street No.10, Hyderabad, Telangana |
|------------------------|---|
| Accreditation Standard | ISO/IEC 17025: 2005 |

Certificate Number TC-7523

Validity 04.07.2018 to 03.07.2020

Page 4 of 6

Last Amended on --

SI. **Product / Material** Test Method Specification **Specific Test** Range of Testing / Performed against which tests are Limits of Detection of Test performed III. METAL AND METAL ALLOYS **Steel Tubes** Yield Stress IS 1608 100 N/mm² to 700 N/mm² 1. Tensile Strength IS 1608 100 N/mm² to1000 N/mm² Elongation IS 1608 2 % to 50 % IS 1161 Mass per meter run 0.1 kg to 30 kg IS 1239 (Part 1) 2. **High Strength** IS 1786 Weight per meter 0.1 kg to15 kg **Deformed Steel** 0.2 % Proof Stress IS 1608 100 N/mm² to 700 N/mm² **Bars And Wires** 100 N/mm² to 900 N/mm² **Tensile Strength** IS 1608 For Concrete Elongation IS 1608 1% to 50% Reinforcement IS 1599 Bend Test Qualitative (Mandrel Dia.: 16 mm 20 mm, 24 mm, 30 mm 32 mm, 36 mm, 40 mm 44 mm, 50 mm, 56 mm 60 mm, 64 mm, 70 mm 75 mm, 84 mm, 100 mm 108 mm, 120 mm, 125 mm 140 mm, 150 mm, 160 mm 175 mm, 192 mm, 224 mm and 256 mm) Re bend Test IS 1786 Qualitative (Mandrel Dia.: 32 mm 40 mm, 44 mm, 50 mm 56 mm, 60 mm, 70 mm 84 mm, 100 mm, 108 mm 120 mm, 140 mm, 150 mm 160 mm, 175 mm, 192 mm 224 mm, 256 mm and 288 mm) 3. IS 808 Structural Steel Weight per meter 0.3 kg to 100 kg IS 1608 Yield Stress 50 N/mm² to 500 N/mm² 100 N/mm² to 700N/mm² Tensile Strength IS 1608

| Lat | poratory | Stedrant Technoclinic Pvt. Ltd, Shed No. F-3/A, IDA Nacharam, Street No.10, Hyderabad, Telangana | | | | | |
|--------------------------------|-------------------------------|--|---|---------------------------------|--|--|--|
| Aco | creditation Standard | ISO/IEC 17025: | ISO/IEC 17025: 2005 | | | | |
| Certificate Number Validity | | TC-7523 | | Page 5 of | f 6 | | |
| | | 04.07.2018 to 03.07.2020 Last Ame | | ended on | | | |
| SI. | Product / Material of Test | Specific Test Performed | Test Method against whi performed | d Specification ch tests are | Range of Testing / Limits of Detection | | |
| [| | Elongation | IS 1608 | | 2% to 50% | | |
| | | Bend Test | IS 1599 | | Qualitative (Mandrel Dia.: 10mm 12mm, 16mm, 18mm 20mm, 24mm, 30mm | | |

32 mm, 36 mm, 40 mm

44 mm, 50 mm, 56 mm 60 mm, 64 mm, 70 mm 75 mm, 84 mm & 100 mm)

| Laboratory | | Stedrant Technoclinic Pvt. Ltd, Shed No. F-3/A, IDA Nacharam, Street No.10, Hyderabad, Telangana | | |
|--------------------|--------------------------------------|--|---|---|
| Acc | reditation Standard | ISO/IEC 17025: 200 | 5 | |
| Certificate Number | | TC-7523 | TC-7523 Page 6 of | |
| Validity | | 04.07.2018 to 03.07. | 04.07.2018 to 03.07.2020 Last Amer | |
| SI. | Product / Material of Test | Specific Test Performed | Test Method Specification against which tests are performed | Range of Testing / Limits of Detection |
| | | NON-DESTR | UCTIVE TESTING | |
| I. | BUILDING MATERIA | LS | | |
| 1. | Reinforced Concrete | Rebound Hammer Test | IS 13311 (Part 2) 1992 (RA 2013) | 10 R Number to 60 R Number |
| | Structures | Ultrasonic Pulse Velocity Test | IS 13311 (Part 1) 1992 (RA 2013) | 2.0 km/sec to 5.0 km/sec |
| | | Cover Meter Test | BS 1881 (Part 204) -1988 | 5 mm to 90 mm |
| | | Carbonation Test | EN 14630-2006 | 1 mm to 40 mm |
| | | Half-cell Potential Measurement Test | ASTM C876-2015 | (-)50 mV to (-) 500mV |
| 2. | Reinforced Concrete Structures | Deflection Measurement Test (Load Test) | IS 456-2000 (RA :2016) | 0.1 mm to 25 mm |